GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notice dated 22nd September 1925.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, up to 24th October 1925, for constructing Chief Operator's Office and Stores at Kolar Gold Fields. The tenders will be opened in public at 2 P.M., on the 26th October 1925. The work should be completed within four months from the date of acceptance of the tender.

2. The plans, detailed estimate and conditions may be obtained at the Chief Electrical Engineer's Office, Bangalore, between the hours of 11 A.M., and 5 P.M., on all working days.

3. Tenders will be submitted on printed forms, which may be obtained from the Office of the Chief Electrical Engineer. The tenders should be accompanied by a statement in the form given below showing the rates, in figures and words, at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for constructing Chief Operator's Office and Stores at Kolar Gold Fields," in default of which tenders will be rejected.

5. The Chief Electrical Engineer reserves the right to accept or reject any tender, or any portion thereof, without assigning any reasons whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board in the Chief Electrical Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money of rejected tenders will be returned.

9. The construction work should be started within fifteen days from the date of notification of the acceptance and completed within four months from the same.

10. Any other conditions that the contractor may wish to state should also be included in his tender.

11. Specifications for work are those recognised by the Mysore Public Works Department.

12. The quantities given below are approximate.

Statement showing the approximate quantities of work for constructing Chief Operator's Office and Stores at Kolar Gold Fields.

No.	Description of items	Per	Quantity
	GROUND FLOOR.		
1	Earthwork excavation in gravelly soil and filling in basement	C.yd.	81
2	Concrete stone jelly in chunam mortar foundation. Stone jelly to be not more than 1½" dia. and the mixture should be 2 of jelly and 1 of mortar. Mortar to be one of lime and two of sand.	C.ft.	709
3	Coursed Rubble stone in mortar, foundation and basement. Mortar to be one lime and two sand.	,,	1,496
4	Burnt brick in mortar, superstructure	,,	3,650
5	Brick in mortar, archwork with centerings	,,	16
6	Stone slabs 6" thick roughly dressed and fixed in mortar	S ft.	273
7	Teakwood wrought and put up with wood oiling 2 coats	C.ft.	49·72
8	Teakwood door panelled 1½" thick shutters with hinges, bolts, etc., complete. (Frames 3" x 5").	S.ft.	68
9	Teakwood door panelled 2" thick with hinges, bolts, etc., complete. (Frames 4" x 6")	,,	60
10	Teakwood windows glazed 1½" thick with iron bars ½" dia., etc., complete	,,	88
11	Teakwood windows glazed 1½" thick with iron bars ½" dia together with 1" mesh expanded metal fixed with battens outside, complete	,,	123
12	Roofing with First Class Mangalore tiles on T. R. 2" x 1"	Sqr.	2·63
13	Roofing with Madras Terrace 9" thick complete with Mangalore tiles flooring and cement pointed on top.	,,	4·11
14	Iron work fixed, complete	Cwts.	39·83
15	Roofing with 24 B. W. G. corrugated galvanized iron sheets with 12" lap at ends and 2 corrugations at sides with lead washers, hook galvanized bolts, nuts, etc., and fixed at eaves with 2" x ¼" strap iron including guy rods at every 10 ft. (The sheets to get 3" into office wall).	Sqr.	13·76
16	Ridge sheeting 36" wide and 15" lap including galvanized bolts, nuts and washers, etc.	R.ft.	43
17	Brick in mortar, cornice 9" deep	,,	60
18	Steel Trusses as per design for a clear span of 22 ft. including hoisting and fixing charges.	No.	2
19	Teakwood ornamental eave boarding 9" x 1" plank	R.ft.	25
20	Chunam plastering 2 coats	Sqrs.	54·62
21	Chunam pointing with lining	,,	4·62
22	White and colour washing 2 coats	,,	54·62
23	Flooring with First Class Mangalore tiles on 3" concrete and cement pointed	,,	3·60

No.	Description of items	Per	Quantity
24	Flooring with Cuddapah slabs 1½" thick on 3" concrete and cement pointed ..	Sqrs.	10·90
25	Expanded metal (1½" mesh) frames with teak battens fixed, complete with a door arrangement including white lead painting 2 coats, complete.	S.ft.	180
26	Binding wall 1½" x 1" brick in mortar with plastering, etc., complete	R.ft.	29
27	Chunam borders at ends 6" x 3"	,,	49
28	Drilling holes in bed slabs of trusses for ¾" dia. bolts	No.	8
29	Silicate painting 3 coats	Sqr.	12·88
30	Stone slabs 4" thick, roughly dressed and fixed in mortar	S.ft.	77
	FIRST FLOOR.		
1	Burnt brick in mortar, superstructure	C.ft.	1,021
2	Stone slabs 6" thick roughly dressed and fixed in mortar	S.ft.	62
3	Teakwood door panelled 1½" shutter with hinges, clamps, bolts, etc., complete ..	,,	28
4	Teakwood windows glazed 1½" shutters with iron bars ¾" dia, complete	,,	105
5	Teakwood ventilators glazed with iron bars	,,	28
6	Teakwood wrought and put up with wood oiling 2 coats	C.ft.	46·79
7	Roofing with First Class Mangalore tiles on T. R. 2" x 1" including cement pointing to roof.	S.qr.	6·00
8	Ridge tiles set in mortar	R.ft.	24
9	Chunam plastering 2 coats	S.qr.	19·54
10	White and colour washing 2 coats	,,	19·54
11	Brick in mortar, binding wall 1½" x 1" including plastering, etc., complete ..	R.ft.	44
12	Ornamental eave guttering of galvanized iron fixed with clamps, etc., complete ..	,,	50
13	Galvanized iron rain water down pipes 4" dia. fixed with clamps, etc., complete ..	,,	120
14	Silicate painting 3 coats	S.qr.	1·89

B. D. NATH,
For *Chief Electrical Engineer.*

MYSORE JAIL.

Notice dated 14th September 1925.

Notice is hereby given that sealed tenders for the supply of dietary articles, etc., required for the use of the Mysore Jail during the Calender year 1926, will be received by the Superintendent, Mysore Jail, on Tuesday, the 10th November 1925, till 9 A.M.

For further particulars, *vide Mysore Gazette*, Part VI of pagees 787—788, dated 24th September 1925.

K. SRINIVASACHAR,
Superintendent.

TUMKUR DISTRICT.

Notice.

An unserviceable Swiss cottage tent of the Deputy Commissioner's Office will be sold by public auction by the Treasury Assistant Commissioner, Tumkur, in the District Office premises on Thursday, the 29th October 1925.

The sale is subject to confirmation by the Deputy Commissioner.

The highest bidder should pay up the full amount of the purchase money at the close of the sale, failing which it will be resold at the risk of the highest bidder in the 1st sale; any loss caused in the 2nd sale will be recoverable from him as an arrear of Land Revenue.

The tent will be placed at the disposal of the purchaser as soon as the sale is confirmed.

S. NARAYAN RAO,
For *Deputy Commissioner.*

OFFICER IN CHARGE, LIVE STOCK SECTION, AGRICULTURAL DEPARTMENT, BANGALORE.

Notice, dated 18th September 1925.

Sealed tenders will be received in the Office of the Live Stock Section, Agricultural Department, Bangalore, for the supply of groundnut oil cake powder, wheat bran, salt, copper-sulphate and ferrous sulphate and rice bran, for the use of the Yellachihalli Sheep Farm, near Mysore, up to 2 P.M. on Saturday the 10th October 1925. The contract will be up to end of June 1926 from date of contract.

Conditions.

1. The tender which should be in the form given below wherein are given the approximate quantity and description of articles required, should state clearly in column 3 of the statement (left blank) the rate at which each article can be supplied at the Farms throughout the year and must be accompanied by samples of each article.

2. Every tender should be accompanied by an earnest money of Rs. 100 either in the form of cash or a cheque on the Imperial or Mysore Banks. The earnest money will be forfeited to Government, if the tenderer, whose tender is accepted, fails to execute the agree-